



**Government of West Bengal**  
Office of the Chief Medical Officer of Health &  
Secretary, District Health & Family Welfare Samiti,  
North 24 Parganas, Kolkata-700124, Ph. No.2552-3129,  
E-mail: cmohn24pgs@gmail.com

**NIT Vide Memo No. CMOH-N24Pgs/ENG-C/1669**

**Date: 22.02.2022**

**N.I.T.No. -06/ENG of 2021-2022**

Sealed tenders are hereby invited by the Chief Medical Officer of Health & Secretary, District Health & Family Welfare Samiti, Barasat, and North 24 Parganas from bona fide, resourceful and responsible contractors / agencies for the Construction work mentioned herein under. Brief details of the work are mentioned at below-

Sl. No	Name of Work	Estimated Cost	Earnest Money	Time of Completion
1	Minor repair, renovation, roof treatment including allied sanitary & plumbing work at DTO office, North 24 Parganas.	Rs.4,86,888.00/- (Including 18% GST)	Rs.9,738/-	15 days
2	Roof casting of the existing asbestos shed portion, out side repairing and construction of surface drain, shed with some allied works at District Chest OPD, North 24 Parganas.	Rs.4,99,642.00/- (Including 18% GST)	Rs.9,993/-	30 days
3	Repair, renovation and extension of District Drug Store (NTEP), North 24 Parganas.	Rs.3,69,098.00/- (Including 18% GST)	Rs.7,382/-	45 days

Date of publication of 'Tender Notice'	Last date of Dropping of 'Sealed Tenders'	Date of opening of 'Technical Bid' & 'Financial Bid'
22.02.2022	03.03.2022 up to 15:00 hrs.	03.03.2022 on 16:00 hrs. at CMOH Chamber

**Terms and Conditions**

1. The interested agencies have to collect their all relevant tender document from <http://north24parganas.gov.in> only.
2. All intending bidders must submit their sealed Tender documents in two separate envelopes for Technical and Financial bids, super-scribed with the addressee, NIT No., Job detail & Agency details are to be dropped in the tender drop box kept in the office of the undersigned on scheduled date and time.
3. Earnest money against the work @ 2.0 % of the total value of work in the form of Demand Draft of a Nationalized Bank/Banker's Cheques in favor of the **District Health and Family Welfare Samiti North 24 Parganas**, payable at Barasat.
4. **Technical Bid contains** Earnest Money DD, Self-declaration form (**Annexure-B**), PAN Card, I.T return of AY- 2021-22, Professional Tax challan of FY 2021-22, GST registration certificate, Valid Trade license in construction of FY 2021-22, Credential document 40% (Forty) of the estimated amount put to tender of similar nature of work during 5(five) years prior to the date of issue of the tender notice and Bye-Laws for Engineer Co-operative/Labour Co-operative society, License under Contract Labour Regulation and Abolition Act 1970.
5. **Financial bid contains** NIT, Estimate of the respective scheme and financial bid document paper. The quoted rate should be in percentage basis, both in figures and in words as per **Annexure-A**.
6. As per GO No 4608-P(Y), Dt. 18.07.2018 from Govt. of W.B. Finance Dept.(Audit Branch), the eligible bidder have to submit addition performance security @ 10% of tender amount if the accepted bid value is 80% or less of the estimate put to tender. The addition performance security shall be submitted in the form of bank guarantee from any nationalized bank within 7 working days from the date of issuance of letter of acceptance, if failed his EMD will be forfeited and other necessary actions like blacklisting of the contractor, etc. may be taken. The bank guarantee will be returned after successful completion of the work. If the bidder fails to complete the work successfully the bank guarantee will be forfeited at any time during the pendency of the contract period after serving proper notice to the contractor.




**Government of West Bengal**  
Office of the Chief Medical Officer of Health &  
Secretary, District Health & Family Welfare Samiti,  
North 24 Parganas, Kolkata-700124, Ph. No.2552-3129,  
E-mail: cmohn24pgs@gmail.com

7. The selected agency have to collect FWD Tender Form No. 2911 from the Engineering section of the undersigned and the same have to be submitted after properly filling-up within 7(Seven) days from the date of receipt of the work order.
8. The authority will not take any responsibility against the amount deposited for earnest money in case of non-submission of bid against the said NIT. In connection with these works, no Arbitration will be allowed.
9. Incomplete tender will be rejected summarily.
10. The work will be executed under the supervision of the engineering section of DPMU. The bidders may collect detail works from the engineering section of DPMU.
11. The offered rate should be inclusive of charges such as royalty & cess, toll charge, carriage, re-carriage, GST etc. No mobilization / secured advance will be allowed.
12. The contractor shall have to carry out work with his own equipment and machinery.
13. The successful tenderer shall have to start the work within **7(seven)** days from the date of issuance of the work order and the work should be completed within the stipulated time, failing which the earnest money may be forfeited and work order will be treated as cancelled.
14. Acceptance of lowest tender is not obligatory & the undersigned reserves the right to accept any tender or to reject any or all tenders at any stage without assigning any reason and to split up tender work's to more than one contractor in the interest of speedy execution of the work. The undersigned reserves the right to alter the terms and condition of this notice at any time in the interest of public service.
15. Total 10% security deposit will be deducted from bill and will be returned after **Defect Liability Period of 1 (one) year for Work Sl No 1 & after 3 (three) years for Work Sl No 2, 3** as per GO No. 5784-PW/L&A/2M-175/2017, Dated- 12/09/2017 of Govt. of West Bengal Law & Arbitration Cell, Public Works Department.  
After successful completion of work the earnest money of successful bidder will be released. No interest should be given on the earnest money & security money.
16. The Earnest money deposited will be forfeited by the Secretary, DH & FW Samiti & C.M.O.H, Barasat, North 24 Parganas in case:-
  - (i) The Tenderer withdraws tender after opening or acceptance.
  - (ii) The selected Tenderer fails to accept order, refuses either wholly or partly the offer that would be made by the undersigned.
  - (iii) The selected Tenderer fails to execute their assigned work within the date stipulated in the work order.
17. Schedule of work /supply will be prepared and measured as per approved P.W.D (W.B) schedule of Rates, Effective from 1<sup>st</sup> November 2017 with all amendments.
18. The undersigned reserves the right to forfeit the Earnest money and security deposited in the event of any short of breach of contract.
19. Contractor should put their firms/organization endorsement (signature of authorized signatory with official stamp) on each page of all the tender documents.
20. Contractors will note that non-compliance of any of the instruction is liable to render there, tender will be non-bona-fide.
21. All kinds of materials and labour related to the job will have to be arranged by the contractor and to be got approved by the engineering section before their use. The contractor at his own cost shall remove the rejected materials/ workmanship from site within 24 hours.
22. The contractors at his cost shall store all the materials which will be used for the work.
23. If the Engineer in charge/Authorized Officer of employer finds that the works delayed by reason beyond the control of the contractor, the Engineer in Charge / Authorized Officer after subjecting the approval of CMOH will make a fair and reasonable extension of time for completion of contract with written approval.
24. The payment of the agency will be released after issuance of work-done satisfactory received from the concerned authority.
25. Contractor have taken requisite "All Risk Insurance Policies" to cover workman under Workman Compensation Act, loss / damage caused by natural calamities / accident /accidental collapse of partially completed work, materials and plant at site and for third party claims for injury / damages.



**Government of West Bengal**  
Office of the Chief Medical Officer of Health &  
Secretary, District Health & Family Welfare Samiti,  
North 24 Parganas, Kolkata-700124, Ph. No.2552-3129,  
E-mail: cmohn24pgs@gmail.com

26. Before taking initiation of any extra item/excess quantity during the work, the same should be got approved by Engineer in charge/Authorized Officer. Payment should be made as per PWD schedule of rate effected from November, 2017 but any extra demand from the work order amount as per tender will not be entertained.
27. Due to work at Hospital the Contractors / agencies will be responsible for work at emergency basis and urgently finishing the work. All materials must be P.W.D. schedule specified, Engineer in charge may ask for test certificates for quality control. The agency/contractor must be carrying the cost of the said test without any claim.
28. Contractors who failed to execute 'Work Orders' issued by this Office in time and such entrusted work(s) is/are yet to be completed and for such delay in execution 'time extension' is not granted by this Office, such contractors or his/her subsidiaries shall not be considered for technical evaluation.


  
Chief Medical Officer of Health  
North 24 Parganas

**NIT Vide Memo No. CMOH-N24Pgs/ENG-C/1669(1/12)**

**Date: 22.02.2022**

Copy forward for kind information and necessary action regarding vast publication to:

1. The Sabhadhipati, 24 Pgs (N) Zilla Parishad.
2. The District Magistrate, North 24 Parganas.
3. The Addl. District Magistrate (D), North 24 Parganas.
4. The Secretary, 24 Pgs (N) Zilla Parishad, with a request to arrange to display the notice in the Office Notice Board.
5. The Dy. CMOH-I, Nodal Officer, North 24 Pgs.
6. The Dy. CMOH-III/ Dy. CMOH-II/ DMCHO/ ZLO/ DTO /Accounts Officer, N24 Pgs.
7. The ACMOH of Barasat Sub-Division, N24Pgs.
8. IT Cell, Swasthya Bhavan, with a request to display the notice in the website.
9. The District Informatics Officer, North 24 Parganas, with the request to upload this notice in the official website of North 24 Parganas health dept.
10. The Admin. Officer, CMOH office, N24Pgs.
11. The DPMU-NHM O/O: CMOH & DH&FWS, N24Pgs.
12. Notice Board.

  
Chief Medical Officer of Health  
North 24 Parganas

*[Handwritten Signature]*  
Chief Medical Officer of Health  
North 24-Parganas.

Self-Declaration

Space for Photograph



I.....son/daughter of Shri.....  
age.....years, resident of..... in the district.....  
of, West Bengal, do hereby declare that the information given above and in  
the enclosed documents is true to the best of my knowledge and belief and  
nothing has been concealed therein. I am well aware of the fact that if the  
information given by me is proved false/ not true at any point of time, I will  
have to face punishment as per any provision of Law for the time being in  
force as well as the benefit availed of by me or the benefit accrued to me shall  
be summarily canceled.

Date:

Signature of Applicant

Place:



**Financial Bid Document**

*[Signature]*  
 Chief Medical Officer of Health  
 North 24-Parganas.

Name of Agency: .....

Address:.....  
 .....

N.I.T No.....of 20....- 20....Vide Memo No: .....

Work Sl. No: .....

Description of Work: .....

Estimated value put to Tender (Rs.): .....

Earnest Money Deposit value (Rs.): .....

Earnest Money Deposit NEFT detail: .....

Quoted Percentage (both in figure and word) if any, to be deducted from bill:  
 .....

(Seal & Signature)

Full Name & Address of the Contractor:

Phone No.:

## Roof treatment with some allied works of DTO office, North 24 Parganas.

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)		
		N	x	L	x	B	x	H					Q	
1	Dismantling all types of masonry excepting cement concrete plain or reinforced, stacking serviceable materials at site and removing rubbish as directed within a lead of 75 m. a) In ground floor including roof. P-10 It-1	Roof	1	x	7.50	x	0.60	x	0.25	1.13	1.13	Cu.M	447.00	502.88
2	Brick work with 1st class bricks in cement mortar (1:6) (b) In superstructure	Wall	1	x	7.50	x	0.25	x	0.50	0.94	0.94	Cu.M	5636.00	5283.75
3	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in 1st floor. Parapet wall	Parapet wall	2	x	2.00	x	0.30			1.20	1.20	Sq.M	748.00	897.60
4	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) .... in ground floor as per relevant IS codes. (i) Pakur Variety		2	x	1.00	x	2.50	x	0.05	0.25	0.25	Cu.M	5586.58	1396.65
5	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including ....(ii) With 1:4 cement mortar 20 mm thick plaster	Outer side wall	2	x	3.50	+	3.50	x	1.2	16.80	16.80	Sq.M	194.00	3259.20
6	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface ..... as per direction of the EIC. In Ground Floor: (a) One Coat	Outer side wall	2	x	3.50	+	14.00	x	2.0	70.00	70.00	Sq.M	31.40	2198.00
7	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per ..... excluding the cost of primer. In Ground floor (Two Coat) b) Premium 100% Acrylic Emulsion	Ground Floor	1	x	70.00					70.00	70.00	Sq.M	84.00	5880.00
8	Cleaning the concrete surface by removing dirt and debris, marking defective locations and removing loose concrete by careful stripping untill hard surface is exposed .... as per direction of the EIC.	Roof	1	x	15.00	x	17.25			258.75	258.75	Sq.M	90.00	23287.50
9	Applying 2 coats of Non-Toxic Acrylic Polymer modified Paint having adhesive & waterproofing properties by mixing in proportion (1 liquid: 4 cementitious material) .... proofing layer in water tank etc.	Roof	1	x	15.00	x	17.25			258.75	258.75	Sq.M	258.00	66757.50
10	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary ..... using cement @ 1.75 kg/sq.m all complete including all materials and labour. 3 mm. thick topping (ii) 25 mm. thick	Roof	1	x	15.00	x	17.25			258.75	258.75	Sq.M	269.00	69603.75
Total .... Rs.												179066.82		
Add. GST @18.0%												32232.03		
Total .... Rs.												211298.85		
Grand Total (rounded off) ..... Rs.												2,11,299/-		

Rupees - Two lakh eleven thousand two hundred ninety nine only.

## Repair, renovation with sanitary &amp; plumbing work at DTO office, North 24 Parganas.

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H					Q
1	Stripping off worn out plaster and raking out joints of walls, cellings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. It-10 P-11	Walls	7	x	1.20	x	1.00		8.40				
			2	x	2.50	x	2.00		10.00				
			4	x	2.00	x	1.50		12.00	30.40	Sq.M	19.00	577.60
2	Dismantling artificial stone flooring upto 50 mm. thick by carefully chiselling without damaging the base and removing rubbish as directed within a lead of 75 m. It-6 P-11	Floor	1	x	4.40	x	5.75		25.30				
			1	x	1.60	x	2.90		4.64				
			1	x	4.00	x	3.15		12.60				
			1	x	5.80	x	2.95		17.11				
			1	x	4.20	x	5.40		22.68	82.33	Sq.M	50.00	4116.50
3	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor ..... of Engineer-in-Charge. (I) With application slurry @1.75 kg/Sq.m, 20 mm sand cement mortar (1:4) .... with pigment (A) Light Colour Item-36 Page-66	Floor	1	x	82.33				82.33				
			1	x	82.33	x	0.30		24.70	107.03	Sq.M	1285.00	137532.27
4	Supplying, fitting & fixing 1st quality Ceramic tiles in walls and floors to match with..... surface, if necessary or by synthetic adhesive & grout materials etc. B) Wall With Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. (b) Area of each tile upto 0.09 Sq.m (ii) Other than Coloured decorative including white Item-36 Page-66	Toilet	4	x	2.40	+ 1.50	x	1.85	28.86	28.86	Sq.M	715.00	20634.90
5	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including ... (ii) With 1:4 cement mortar (a) 15 mm. thick plaster at 1st floor Item-1 Page-189	Inside walls	7	x	1.20	x	1.00		8.40				
			6	x	2.50	x	1.80		27.00	35.40	Sq.M	167.00	5911.80
6	Supplying, Fitting & Fixing Factory made prelaminate P.V.C. door frame of size 50 mmx47 mm with a wall thickness of 5 mm .... complete as per Manufacturer's specification and direction of EIC. It-5 P-116		2	x	5.00				10.00	10.00	Mtr.	385.00	3850.00
7	Supplying, Fitting & Fixing 30 mm thick Factory made solid Panel PVC Door Shutter consisting of outer frame made out of M.S. tubes of 19 gauge thickness and size 19 mmx19 mm for styles, top and bottom rails ..... direction of EIC. It-5 P-		2	x	2.05	x	0.75		3.08	3.08	Sq.M	1943.00	5974.73
8	Supplying, fitting and fixing bib cock or stop cock. (a) (i) Chromium plated Bib Cock short body (Equivalent to Code No. 511 & Model - Tropical/Sumthing .... ESSCO or similar brand) It-5 P-116		5	x	1.00				5.00	5.00	Each	539.00	2695.00
9	Supplying, fitting and fixing 10 litre porcelain low-down cistern of approved make without fittings and brackets. White S&P- It-3 P-36		2	x	1.00				2.00	2.00	Each	1367.00	2734.00
10	Supplying, fitting and fixing towel rail with two brackets. (a) C.P. over brass (iii) 25 mm dia. and 750 mm long S&P It-22 P-82		3	x	1.00				2.00	2.00	Each	475.00	950.00
11	Applying interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive ..... as per direction of the EIC. (a) One Coat (ii) Solvent based interior grade Acrylic Primer Item-7 Page-195	Inside Walls	1	x	135.00	x	2.70		364.50	364.50	Sq.M	33.70	12283.65

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)
		N	x	L	x	B	x	H				
12	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer ..... including cleaning and smoothing of surface. Two Coats It-10 P-196											
	Ground Floor Priming area	1	x	364.50				364.50	364.50	Sq.M	70.00	25515.00
13	(a) Priming one coat on steel and other metal surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. Item-1 Page-200											
	Gate	2	x	2.1	x	1.20	x	2.20	11.09			
	Walls	18	x	2.1	x	1.20			45.36			
								56.45	56.45	Sq.M	29.00	1636.99
14	(A) Painting with best quality synthetic enamel paint of approved make and brand .... necessary : (b) On steel and other metal surface : With super gloss (hi-gloss) (iv) Two coats (with any shade except white) Item-2 Page-200											
	Priming area	1	x	56.45				56.45	56.45	Sq.M	79.00	4459.39
15	(b) Priming one coat on timber or plastered surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. Item-1 Page-200											
	Door	6	x	2.1	x	1.20	x	2.60	39.31			
								39.31	39.31	Sq.M	38.00	1493.86
16	(A) Painting with best quality synthetic enamel paint of approved make and brand .... necessary : (a) On timber or plastered surface : With super gloss (hi-gloss) (iv) Two coats (with any shade except white) Item-2 Page-200											
	Priming area	1	x	39.31				39.31	39.31	Sq.M	81.00	3184.27
<b>Total .... Rs.</b>											<b>233549.95</b>	
Add. GST @18.0%											42038.99	
<b>Total .... Rs.</b>											<b>275588.94</b>	
<b>Grand Total (rounded off) ..... Rs.</b>											<b>2,75,589/-</b>	
<b>Rupees - Two lakh seventy five thousand five hundred eighty nine only.</b>												

21.02.22  
 ENG. ...  
 ...

By: CMOH - I  
 Nodal Officer of Construction.  
 North 24 Parganas



## Roof casting of the existing asbestos shed portion with some allied works of DTO office, North 24 Parganas.

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H					Q
1	Taking out carefully G.C.I. or C.I. or asbestos sheets (including ridges etc.) from roof or wall after unscrewing bolts, nuts, screws etc. and stacking the material at site as directed. P-11 It-8	shed	1	x	4.00	x	11.50		46.00				
								46.00	Sq.M	41.00	1886.00		
2	Dismantling carefully wood work in posts, postplates, rafters, partition etc., sorting and stacking servicable materials at site and removing rubbish as directed. It-19 P-13	Shed	11	x	4.00	x	0.10	x	0.06	0.26			
			12	x	3.50	x	0.10	x	0.06	0.25			
								0.52	Cu.M	278.00	143.45		
3	Brick work with 1st class bricks in cement mortar (1:6) It-8 P-15	(a) In foundation or trenches	2	x	1.50	x	0.250	x	0.25	0.19			
								0.19	Cu.M	5413.00	1014.94		
		(b) In superstructure	Wall	1	x	18.00	x	0.25	x	1.00	4.50		
								4.50	Cu.M	5636.00	25362.00		
4	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in 1st floor. Item-16 Page-16	Parapet wall	1	x	18.00	x	0.30		5.40				
								5.40	Sq.M	748.00	4039.20		
5	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) .... in ground floor as per relevant IS codes. (i) Pakur Variety Item-4 Page-24		1	x	3.00	x	4.00	x	0.075	0.90			
								0.90	Cu.M	5586.58	5027.92		
6	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety It-10 P-26	Lintel	1	x	18.00	x	0.250	x	0.150	0.68			
		Chajja	1	x	18.00	x	0.50	x	0.075	0.68			
		Roof Beam	1	x	24.00	x	0.25	x	0.200	1.20			
		Salb	1	x	3.50	x	11.50	x	0.125	5.03			
								7.58	Cu.M	6133.45	46499.22		
7	Hire and labour charges for shuttering with centering and necessary staging upto 4 m .... (a) 25 mm to 30 mm thick wooden shuttering ..... Engineer-In-Charge. Item-36 Page-42	Lintel	2	x	18.00	x	0.150		5.40				
		Chajja	1	x	18.00	x	0.500		9.00				
		Roof Beam	2	x	24.00	x	0.20		9.60				
		Slab	1	x	3.50	x	11.50		40.25				
			2	x	3.50	x	0.125		0.88				
			2	x	11.50	x	0.125		2.88				
								68.00	Sq.M	353.00	24004.00		
8	Reinforcement for reinforced concrete work in all sorts of structures including .... 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (i) Tor steel/Mild Steel III. JSW/JSPL/SHYAM/SRMB/BMASL/ELECTROSTEEL/SSL Item-40 Page-44				7.58	x	1.0/100x7.850		0.60	0.60	M.T.	54586.07	32485.71
9	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor ..... of Engineer-in-Charge. (i) With application slurry @1.75 kg/Sq.m, 20 mm sand cement mortar (1:4) .... with pigment (A) Light Colour Item-36 Page-66	Floor	1	x	3.00	x	11.00		33.00				
			2	x	3.00	+ 11.00	x	0.15	6.30				
								39.30	Sq.M	1285.00	50500.50		

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H					Q
10	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including ....(ii) With 1:4 cement mortar (a) 15 mm. thick plaster at 1st floor Item-1 Page-189												
	In side walls	2	x{	3.00	+	11.00	}x	1.00	28.00	28.00	Sq.M	167.00	4676.00
	(b) 20 mm thick plaster Outer side wall	2	x{	3.50	+	11.50	}x	3.0	90.00	90.00	Sq.M	194.00	17460.00
	(C) 10 mm thick plaster Ceiling	1	x	3.00	x	11.00			33.00	33.00	Sq.M	133.00	4389.00
11	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive ..... as per direction of the EIC. (a) One Coat (ii) Solvent based interior grade Acrylic Primer Item-7 Page-195												
	Inside plaster	1	x	28.00					28.00				
		1	x	33.00					33.00				
		2	x{	3.00	+	11.00	}x	2.0	56.00	117.00	Sq.M	33.70	3942.90
12	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface ..... as per direction of the EIC. In Ground Floor: (a) One Coat Item-8 Page-196												
	Outer side wall	2	x{	3.50	+	11.50	}x	4.0	120.00	120.00	Sq.M	31.40	3768.00
13	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer ..... Including cleaning and smoothing of surface. Two Coats It-10 P-196												
	Ground Floor Priming area	1	x	117.00					117.00	117.00	Sq.M	70.00	8190.00
14	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per ..... excluding the cost of primer. In Ground floor (Two Coat) b) Premium 100% Acrylic Emulsion Item-17 Page-197												
	Ground Floor Priming area	1	x	120.00					120.00	120.00	Sq.M	84.00	10080.00
15	(a) Priming one coat on steel and other metal surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. Item-1 Page-200												
	Gate	2	x	2.1	x	1.20	x	2.20	11.09				
		8	x	1.2	x	1.20	x	2.20	25.34				
									36.43	Sq.M	29.00	1056.53	
16	(A) Painting with best quality synthetic enamel paint of approved make and brand .... necessary : (b) On steel and other metal surface : With super gloss (hi-gloss) (iv) Two coats (with any shade except white) Item-2 Page-200												
	Priming area	1	x	36.43					36.43	36.43	Sq.M	79.00	2878.13
											Total .... Rs.	247403.49	
											Add. GST @18.0%	44532.63	
											Total ....Rs.	291936.11	
											Grand Total (rounded off) ..... Rs.	2,91,936/-	

Rupees - Two lakh ninety one thousand nine hundred thirty six only.

21.02.22  
SAE (Civil), DMPL  
NH&M, DM'S PWS, 24 PGS (N)

22/2/22  
Dy. CMOH - I  
Nodal Officer of Construction,  
North 24 Parganas

**Out side repair and new construction of surface drain, shed with some allied works at DTO office, North 24 Parganas.**

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H					Q
1	Stripping off worn out plaster and raking out joints of walls, ceilings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed. It-10 P-11												
	Walls	5	x	8.50	x	1.00		42.50					
		4	x	2.50	x	1.40		14.00					
		6	x	5.00	x	1.50		45.00	101.50	Sq.M	19.00	1928.50	
2	Brick work with 1st class bricks in cement mortar (1:6) (b) In superstructure It-8 P-15												
		2	x	25.00	x	0.25	x	0.25	3.13	3.13	Cu.M	5636.00	17612.50
3	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand. It-1 P-14												
		1	x	25.00	x	0.75		18.75	18.75	Sq.M	361.00	6768.75	
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including ... (ii) With 1:4 cement mortar (b) 20 mm. thick plaster at 1st floor Item-1 Page-189												
		1	x	101.50	+	45.00		146.50	146.50	Sq.M	194.00	28421.00	
5	Supplying, fitting & fixing UPVC pipes A- Type and fittings conforming to IS:13592-1992 with all necessary ..... including joining with jointing materials (Spun Yarn, Valamold/ Bitumen/M-Seal etc) complete. A) UPVC Pipes: (ii) 110 mm. Dia. It-21 P-212												
		1	x	18.00				18.00	18.00	Sq.M	167.00	3006.00	
6	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive ... preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: (a) One Coat It-8 P-196												
		2	X	( 15.00 + 12.00 )	x	5.0		270.00	270.00	%Sq.M	3140.00	8478.00	
7	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive ... preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. In Ground Floor: (a) One Coat It-8 P-196												
		2	X	( 15.00 + 12.00 )	x	5.0		270.00	270.00	%Sq.M	3140.00	8478.00	
8	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification ..... all incidental charges but excluding the cost of primer. In Ground floor (Two Coat) b) Premium 100% Acrylic Emulsion It-17 P-197												
		1	x	270.00				270.00	270.00	Sq.M	84.00	22680.00	
9	(a) Priming one coat on steel and other metal surface with synthetic oil bound primer of approved quality including smoothing surfaces by sand papering etc. Item-1 Page-200												
	Gate	2	x	2.1	x	1.20	x	2.20	11.09				
	Walls	18	x	2.1	x	1.00		37.80					
								48.89	48.89	Sq.M	29.00	1417.75	
10	(A) Painting with best quality synthetic enamel paint of approved make and brand .... necessary : (b) On steel and other metal surface : With super gloss (hi-gloss) (iv) Two coats (with any shade except white) Item-2 Page-200												
	Priming area	1	x	48.89				48.89	48.89	Sq.M	79.00	3862.15	
11	Construction of circular soak well 2.5 metre deep in all types of sandy soils with dry brick work upto 1.6 metre from the bottom having 150 mm ..... With 250 mm thick dry brick work and 250 mm thick cement brick work (1:6) and 1.00m inside dia. With JSW/ISPL/SHYAM/ SRMB ...../SSL												
		1	X	1.00				1.00	1.00	Each	16621.00	16621.00	
12	Supplying, fitting & fixing Zn-Al alloy (55% Al & 45% Zn) coating of 150 grams per sq. meter (followed by colour coated on both side) steel sheet work .... minimum side lap. (i) In Roof: a) With 0.5 mm thick sheet It-14 P-82												
		1	x	10.00	x	4.50		45.00	45.00	Sq.M	787.00	35415.00	

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)
		N	x	L	x	B	x	H				
13	M.S. structural works with hollow sections ( square or rectangular shape) conforming to IS: 806-1957 & IS:1161-1958) connected to one another with bracket, gusset, cleat as per design .... hoisting and erection all complete. ii) For other Structural works like galleries etc. It-2A P-101											
	40 mm & 25 mm square hollow bar	1	x	0.295				0.295	0.30	M.T.	72316.00	21333.22
<b>Total</b>											<b>176021.87</b>	
Add. GST @18.0%											31683.94	
<b>Total</b>											<b>207705.81</b>	
<b>Grand Total (rounded off) ..... Rs.</b>											<b>2,07,706/-</b>	
<b>Rupees - Two lakh seven thousand seven hundred six only.</b>												

21.02.22  
 Dy. CMOH - I  
 North 24 Parganas

21.02.22  
 Dy. CMOH - I  
 Nodal Officer of Construction  
 North 24 Parganas

## Repair, renovation and extension of District Drug Store (NTEP), North 24 Parganas.

It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)		
		N	x	L	x	B	x	H					Q	
1	Earth work in excavation of foundation trenches or drains, in all sorts of soil .... including removing, spreading or stacking the spoils within a lead of 75 m. as directed. The item includes necessary trimming the sides of trenches, levelling, dressing and ramming the bottom, bailing out water as required complete. (a) Depth of excavation not exceeding 1,500 mm. It-2 P-1	Footing	6	x	1.20	x	1.20	x	1.2	10.37				
									10.37	%Cu.M	11927.00	1236.59		
2	Earth work in filling in compound, tank, low land, ditches etc. with good earth, in layers not exceeding 150 mm. including breaking clods and consolidating the same by ramming and dressing complete. i) With carried earth arranged by the contractor within a radius exceeding 3 km. but not exceeding 5km. including the cost of carried earth. It-3 P-1	Footing	6	x	1.20	x	1.20	x	0.60	8.64				
		Floor	1	x	6.25	x	3.00	x	0.30	2.78				
									11.42	%Cu.M	41958.00	4789.51		
3	Single Brick Flat Soling of picked Jhama bricks including ramming ..... joints with local sand. It-1 Pg-14	Footing	6	x	1.20	x	1.20			8.64				
		Floor	1	x	3.50	x	6.75			23.63				
									32.27	Sq.M	361.00	11647.67		
4	Brick work with 1st class bricks in cement mortar (1:6) (a) In foundation or trenches It-8 P-15	Steps	4	x	1.50	x	0.250	x	0.15	0.23				
									1.35	Cu.M	5413.00	7307.55		
	(b) In superstructure	Wall	1	x	18.00	x	0.25	x	2.70	12.15				
		Less Gate	1	x	2.25	x	0.25	x	1.20	-0.68				
									11.48	Cu.M	5636.00	64673.10		
5	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in 1st floor. Item-15 Page-16	Parapet wall	1	x	18.00	x	0.30			5.40				
									5.40	Sq.M	748.00	4039.20		
6	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) .... in ground floor as per relevant IS codes. (i) Pakur Variety Item-4 Page-24	Footing	6	x	1.20	x	1.20	x	0.075	0.65				
		Floor	1	x	3.00	x	6.25	x	0.075	1.41				
									2.05	Cu.M	5586.58	11476.23		
7	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety It-10 P-26	Footing	6	x	1.05	x	1.05	x	0.185	1.22				
			6	x	0.60	x	0.60	x	0.150	0.32				
		Column	6	x	4.00	x	0.25	x	0.25	1.50				
		Lintel	1	x	18.00	x	0.250	x	0.150	0.68				
		Chajja	1	x	4.50	x	0.50	x	0.075	0.17				
		Tie Beam	1	x	18.00	x	0.25	x	0.250	1.13				
		Roof Beam	1	x	21.00	x	0.25	x	0.150	0.79				
		Salb	1	x	7.05	x	3.80	x	0.120	3.21				
									9.02	Cu.M	6133.45	55316.51		
8	Hire and labour charges for shuttering with centering and necessary staging upto 4 m .... (a) 25 mm to 30 mm thick wooden shuttering ..... Engineer-In-Charge. Item-36 Page-42	Footing	6	x	4.20	x	0.20			5.04				
		Column	6	x	4.00	x	1.00			24.00				
		Lintel	2	x	18.00	x	0.150			5.40				
		Chajja	1	x	4.50	x	0.500			2.25				
		Tie Beam	2	x	18.00	x	0.250			9.00				
		Roof Beam	2	x	21.00	x	0.15			6.30				
		Slab	1	x	7.05	x	3.80			26.79				
			2	x	7.05	x	0.120			1.69				
			2	x	3.80	x	0.120			0.91				
									81.38	Sq.M	353.00	28728.55		



It. No.	Item of work	Measurement							Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H					Q
9	Reinforcement for reinforced concrete work in all sorts of structures including ..... 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (i) Tor steel/Mild Steel III. JSW//JSPL//SHYAM//SRMB//BMAASL//ELECTROSTEEL//SSL Item-40 Page-44			9.02	x	1.0/100x7.850			0.71	0.71	M.T.	54586.07	38645.72
11	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) In floor ..... of Engineer-in-Charge. (i) With application slurry @1.75 kg/Sq.m, 20 mm sand cement mortar (1:4) .... with pigment (A) Light Colour Item-36 Page-66	Floor	1	x	6.25	x	3.00		18.75				
			2	x	6.25	+	3.00	]x	0.15	7.15			
									25.90	Sq.M	1285.00	33281.50	
12	(a) M.S.or W.I. Ornamental grill of approved design joints continuously welded with ..... lugs in ground floor. (i) Grill weighing above 10 Kg./sq.mtr and up to 16 Kg./sq. mtr. Item-13 Page-104 (b) Extra for work in grill gate. (i) For hanging and locking arrangements including supply of materials and labour complete.	Gate	1	x	2.10	x	1.00	x	12/100	0.25			
										0.25	Qntl.	9888.00	2491.78
13	Supplying 1.5mm thick M.S. sheet fitted and fixed on one or both faces of M.S./ W.I. gate etc. with point welding at not more than 150mm ..... all labour and materials. Item-15 Page-105	gate	1	x	2.10	x	1.00		2.10				
									2.10	Sq.M	1304.00	2738.40	
24	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including ... (ii) With 1:4 cement mortar (a) 15 mm. thick plaster at 1st floor Item-1 Page-189	In side walls	2	x	3.00	+	6.25	]x	2.85	52.73	Sq.M	167.00	8805.08
	(b) 20 mm thick plaster	Outer side wall	2	x	3.50	+	6.75	]x	4.0	82.00			
									82.00	Sq.M	194.00	15908.00	
	(C) 10 mm thick plaster	Ceiling	1	x	3.60	x	6.55		23.58	23.58	Sq.M	133.00	3136.14
15	Applying interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive ..... as per direction of the EIC. (a) One Coat ii) Solvent based interior grade Acrylic Primer Item-7 Page-195	Inside plaster	1	x	52.73				52.73				
			1	x	23.58				23.58				
									76.31	Sq.M	33.70	2571.48	
16	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface ..... as per direction of the EIC. In Ground Floor: (a) One Coat Item-8 Page-196	Outer side wall	1	x	82.00				82.00	Sq.M	31.40	2574.80	
17	Acrylic Distemper to interior wall, ceiling with a coat of solvent based interior grade acrylic primer .... including cleaning and smoothing of surface. Two Coats It-10 P-196	Ground Floor	Priming area	1	x	76.31			76.31	76.31	Sq.M	70.00	5341.35
18	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per ..... excluding the cost of primer. In Ground floor (Two Coat) b) Premium 100% Acrylic Emulsion Item-17 Page-197	Ground Floor	Priming area	1	x	82.00			82.00	82.00	Sq.M	84.00	6888.00

It. No.	Item of work	Measurement								Total	Unit	Rate	Amount (Rs.)	
		N	x	L	x	B	x	H	Q					
19	(a) Priming one coat on steel and other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. Item-1 Page-200	Gate	2	x	2.1	x	1.20	x	2.20	11.09	11.09	Sq.M	29.00	321.55
20	(A) Painting with best quality synthetic enamel paint of approved make and brand .... necessary : (b) On steel and other metal surface : With super gloss (hi-gloss) (iv) Two coats (with any shade except white) Item-2 Page-200	Priming area	1	x	11.09					11.09	11.09	Sq.M	79.00	875.95
<b>Total ..... Rs.</b>													<b>312794.66</b>	
Add. GST @18.0%													56303.04	
<b>Total ..... Rs.</b>													<b>369097.69</b>	
<b>Grand Total (rounded off) ..... Rs.</b>													<b>3,69,098/-</b>	
<b>Rupees - Three lakh sixty nine thousand ninety eight only.</b>														

21.02.22  
 CTE  
 2022

*[Signature]*  
 Dy. CMOH - I  
 nodal Officer of Construction  
 North 24 Parganas